

足場工供用月数

設置期間 =	地組工	+	支承工	+	桁架設工	+	溶接工	+
	本締工	+	塗装工	+	排水管	+	地覆工	
	足場工	) ×	1.7					
= (	0.0	+	0.0	+	5.5	+	19.0	+
	5.4	+	29.0	+	1.1	+	2.6	
	8.1	) ×	1.7					
=	120.2	日	=	4.0	月			